

PERFORMANCE WORK STATEMENT

Performance Work Statement (PWS) Building, Sports Field, and Playground Maintenance Services Pacific East

1. General Information and Scope of Work.

1.1. Agency. The Department of Defense Education Activity (DoDEA), as one of only two Federally operated school systems, is responsible for planning, directing, coordinating, and managing prekindergarten through 12th grade educational programs on behalf of the Department of Defense (DoD). DoDEA is globally positioned, operating 160 brick-and-mortar schools in eight districts located in seven states, 11 foreign countries, Guam, and Puerto Rico. DoDEA employs over 8,000 educators who serve more than 72,000 children. DoDEA also has a fully accredited virtual high school located in Virginia with teaching hubs in Europe and the Pacific.

1.2. Introduction. The following maintenance services are required to maintain a safe, healthy, and sanitary school environment for faculty and students within the Department of Defense Education Activity (DoDEA) Pacific East District (Japan). The contractor shall provide all management, tools, equipment, labor, and transportation necessary to ensure that maintenance services are performed in accordance with the objectives and standards outlined within this PWS. Therefore, this requirement calls for the continuous efforts on the part of the contractor to ensure appropriate safety and functionality of facilities are maintained throughout the life of the contract.

1.3. Background. The Department of Defense Education Activity (DoDEA) Pacific East District (Japan) is composed of 20 schools, the District Superintendent's Office (DSO) and the Student Transportation Office (STO). However, this PWS covers only eight schools in the Kanto Plain and Tohoku regions. DoDEA instructional program provides a comprehensive prekindergarten through 12th grade curriculum that is dedicated to attaining the highest student achievement for children of active-duty military and eligible civilian employees.

1.4. Scope of Work. The contractor will be required to provide and manage a full-service Facility Maintenance, Heating, Ventilation, Air Conditioning and Refrigeration (HVACR) Maintenance, and Sports Fields and Playgrounds Maintenance program for the Pacific East District, located in Japan. The major elements of the services required include:

- a. Facility Maintenance
- b. Heating, Ventilation, Air Conditioning and Refrigeration (HVACR) Maintenance
- c. Sports Fields and Playgrounds Maintenance
- d. Non-Routine Work Request.

2. Requirements & Objectives. The contractor is expected to develop the total solution for meeting all of the following requirements and objectives in accordance with a performance-based approach. The government reserves the right to incorporate the winning offeror's proposed technical response into the contract.

2.1. Facility Maintenance (Objective 1)

The objective is to develop, maintain, sustain and perform a comprehensive facility maintenance program for items listed in Attachments 1, 2 and 3 of the PWS in order to preserve the quality of facility equipment, real property installed, components and systems to manufacturer standards through functional checks, servicing, repairing, and/or replacing.

2.1.1. Frequency. Frequency of the overall Facility Maintenance objective will be established by the Preventive Maintenance Plan. The Preventive Maintenance Plan shall establish the Contractor's course of action for effectively

and efficiently meeting manufacture recommendations and standards, to include frequencies for proactively performing maintenance, repairs, and replacements in order to prevent failures.

2.1.2. Performance Standard. Performance standard for services rendered under the Facility Maintenance objective is based on adhering to the established performance frequencies. Deviation from adhering to the established performance frequencies shall result in no more than five verified complaints per month. The tasks listed below are provided to help the contractor in gaining a better understanding of the requirements in order to successfully meet the objective. The tasks are not all inclusive as the contractor is expected to develop the total solution for meeting all the requirements of the objective in accordance with a performance-based approach.

2.1.3. Routine Facility Maintenance. The objective is to provide routine, recurring facility maintenance services regarding electrical, mechanical, civil and structural disciplines in accordance with equipment and systems manufacturer recommendation via vigilant routine inspections.

The objective includes performing minor work and repairs, defined as work that the Contractor will expend \$2,500.00 or less in material costs and includes inspection, periodic and preventive maintenance, operation of utilities and minor repairs incidental to schedule. Excludes damages and/or malfunctions caused by vandalism and natural disasters. Any repairs exceeding \$2,500.00 in material cost shall be identified as a non-routine work request, subject to COR's review and approval.

2.1.4. Exterior Facility Management. The objective is to maintain exterior equipment, systems and property listed in Attachments 1, 2 and 3 of the PWS by conducting monthly unless the Preventive Maintenance Plan, manufacturer's recommendations or industry standards dictate a more frequent interval between inspections, at which time the more frequent interval shall be followed.

Below are examples of, but not limited to, the types of exterior facility, equipment and systems that require routine inspections and corrective action.

- a. Sanitary Sewer Systems
- b. Water Distribution Systems, and record meter levels if available
- c. Electrical Distribution Systems, and record meter levels if available
- d. Exterior lights
- e. Radon Mitigation Systems, inspect for damage and functionality, and record meter levels if available
- f. Liquid Propane Gas (LPG) Systems, and record meter levels if available
- g. Storm drains, gutters, catch basins, traps and grates
- h. Chiller yards, LPG storage, transformer yards and atriums free of debris, weeds and are aesthetically pleasing
- i. Facility walls, covered walkways and staircases
- j. Painted surfaces (Removal of mold, mildew, and stains.
- k. Windows, window frames, light/storm shelves, screens and caulking
- l. Public Announcement (PA) system, speakers, bells, clocks, marquees, and scoreboards.
- m. Playground equipment (limited to elementary and primary schools), play courts and general play (DoDEA standards)
- n. Asphalt, concrete and play surfaces free from mold, stains, debris, holes, uneven or other conditions that pose a hazard to personal safety or property. (Pressure washing)
- o. Parking, bus loading and safety area markings and signage to ensure they are properly marked and visible for their intended purpose. (painting)
- p. Fences, gates and entrances
- q. Picnic tables, benches, grandstands and other outdoor fixed furniture
- r. Restrooms, water fountains and irrigation systems

2.1.5. Interior Facility Maintenance. The objective is to maintain interior equipment, systems and property listed in Attachments 1 and 2 of the PWS by conducting monthly inspections unless the Preventive Maintenance Plan, manufacturer's recommendations or industry standards dictate a more frequent interval between inspections, at which time the more frequent interval shall be followed. At the request of the COR, an inspection or repair of specific

equipment or system may be required.

Below are examples of, but not limited to, the types of interior facility, equipment and systems that require routine inspections, mounting or corrective action.

- a. Windows, blinds, drapery, panels and hardware for missing components and proper operation
- b. Doors, locks and hardware, including standard key and CorKey systems
- c. Entrances, lighting, air curtains and weather stripping
- d. Wall surfaces, partitions or built-in room dividers are operational and free of damage, deterioration and required painting
- e. Fire extinguishers and Fire Suppression Systems, inspect for damage and functionality, and record meter levels and expiration dates if available
- f. Ceilings, lighting, tiles, concrete and other surfaces are missing, damaged or stained and free from hazardous and unsightly conditions
- g. Staircases, hand-railing, safety strips and fixtures are secure and free from hazardous conditions
- h. Display cases, signage, white/cork/chalk boards
- i. Smart boards, Video Teleconference, countertops, shelves
- j. Sinks, water fountains, motion sensor plumbing fixtures, drains, traps and grates
- k. Floors, ceramic, cover base, tile, vinyl, wood, concrete and other are missing, damaged, stained, secure and present a flat uniform surface free from hazardous and unsightly conditions
- l. Lockers, cabinets, counters and architectural woodwork for damage, deterioration and functionality
- m. Basketball backboards, goals, bleachers, supporting posts, nets and other athletic mechanisms within the gym are mounted, operational and free of damage and deterioration that would cause a hazardous condition
- n. Bathroom toilets, urinals, motion sensor plumbing fixtures, mirrors, stalls and other fixtures are operational and free from damage, deterioration and required painting
- o. Miscellaneous facility maintenance equipment maintained by the schools and facilities, power washers, dollies, forklifts, hydraulic lifts, pallet jacks, carpet cleaner, carpet driers, wet vacuum, and genie lift.
- p. Identification and assessment of mold and corrective action as required

2.1.6. Emergency Facility Maintenance. The Contractor shall respond to any emergency requests for facility maintenance within two (2) hours and sufficiently resolve the emergency situation within one calendar day of notification. Upon stabilizing the emergency, any additional required maintenance required on Pacific East District (Japan) facilities will be further categorized as either Routine Maintenance or Non-Routine Work Request.

2.2. Heating, Ventilation, Air Conditioning and Refrigeration (HVACR) Maintenance (Objective 2)

The objective is to develop, maintain, sustain and perform a comprehensive HVACR maintenance program for all HVACR equipment identified in Attachments 1 and 2 of the PWS in order to preserve the quality of HVACR equipment, components and systems to manufacturer standards through functional checks, servicing, repairing, and/or replacing.

2.2.1. Frequency. Frequency of the overall Heating, Ventilation, Air Conditioning and Refrigeration (HVACR) Maintenance objective will be established by the Preventive Maintenance Plan. The Preventive Maintenance Plan shall establish the Contractor's course of action for effectively and efficiently meeting manufacturer recommendations and standards, to include frequencies for proactively performing maintenance, repairs, and replacements in order to prevent failures.

2.2.2. Performance Standard. Performance standard for services rendered under the Facility Maintenance objective is based on adhering to the established performance frequencies. Deviation from adhering to the established performance frequencies shall result in no more than five verified complaints per month. The tasks listed below are provided to help the contractor in gaining a better understanding of the requirements in order to successfully meet the objective. The tasks are not all inclusive as the contractor is expected to develop the total solution for meeting all the requirements of the objective in accordance with a performance-based approach.

2.2.3. Routine HVACR Maintenance. The objective is to provide routine, recurring preventive maintenance

services for allHVACR systems regarding electrical, mechanical, civil and structural disciplines in accordance with equipment, systems manufacturer recommendation and the Preventive Maintenance Plan. The objective includes performing minor work and repairs, defined as work that the Contractor will expend \$2,500.00 or less in material costs and includes inspection, periodic and preventive maintenance, operation of utilities and minor repairs incidental to schedule. Excludes damages and/or malfunctions caused by vandalism and natural disasters. Any repairs exceeding\$2,500.00 in material cost shall be identified as a non-routine work request, subject to COR's review and approval.

2.2.3.1. General Requirements of Routine HVACR Maintenance.

Regular Adjustments: Regular adjustments are required for efficient, economical and safe performance of equipment will be made at the time of each scheduled preventive maintenance and service visit.

Lubrication: Verify the manufacturer's lubrication instructions to ensure each piece of equipment has the proper amount of oil and add or remove as required. Lubricate if a grease dispenser or oil cup is less than half full of manufactures recommendations; change oil when it becomes dirty and clean all clogged oil lines.

Compressor oil will be changed every time housing is "broken" for any reason. The contractor shall clean, check and repack all bearings in accordance with the manufacturer's instructions.

Periodic Cleaning and Sanitation: Cleaning of work areas and mechanical equipment rooms, systems, drains, drain piping, blow downs, traps, strainers, and pans, condenser coils, oil filters, applicable air filters, air vents, grills, diffusers, screens, ducts, dampers, registers, ERV's, cooling and/or heating coils, blower shields and fans, electric contacts, switch boxes, motors, gauges, pressure and electric sensors, thermostatic devices, actuators, louvers, safety controls, and any other applicable equipment will be accomplished as a part of the regular scheduled preventive maintenance visit, or more frequently, if required, to maintain clean, sanitary and operating conditions.

Replacement and Cleaning of Air Filters: The servicing of air filters, a minimum of once a month, will include: check for dirt, grease and other deposits and for missing or improperly fitted filters, replace dirty throw-away type filters and those having improper fit, wash permanent type filters in soap solution or solvent, rinse with water and restore viscous coating in accordance with the manufacturer's instructions. Permanent washable filters will be replaced, by the contractor at no additional cost to the Government, when cleaning is no longer an effective solution to airflow problems. Blowers will not be in operation when cleaning or changing filters.

Rust and Corrosion: Remove all rust from all metal surfaces of all air conditioning units, ERV's, roof and wall support stands, air handlers, ventilators, exposed duct, condensation pans, pump casings, water tanks, exposed piping, boilers and electric water heaters. Replace metal sections having advanced corrosion. Apply one (1) coat of rust inhibiting primer followed by two (2) finish coats matching the existing paint color and type. These procedures will be performed any time during the year when the contractor, and COR notes rust and corrosion.

Coils: Check for obstructions to airflow through all coils. Check for dust, dirt, foreign material accumulation, unusual noises, vibrations, and loose, missing or damaged parts. On direct expansion systems, check for frosting or icing ofcoils; proper operation of expansion valves, capillary tubes, and proper spacing of spider distributors; proper operation of automatic temperature controls and check superheat across evaporator coils. Check all coils for leaks. On water cooling/heating coils, correct any deficiencies not allowing for proper operation. Check damaged bent or corroded coil fins on all coils. Clean, adjust, service, repair or replace items found to be deficient.

Condensation Drains, Pans, Piping and Traps: Check all condensation drain pans for algae growth, sedimentation, damaged coatings, damaged insulation, rust, corrosion and leaks. Check condensation drainpipes and traps to insure they are open and water flow is not restricted. Clean, adjust, service, repair and/or replace items found to be deficient.

Piping-Water, Oil, Refrigerant and Air: Check for leaks, rust, corrosion, deformation and material defects of all applicable piping and tubing. Check for vibrations, looseness and rubbing against objects that can cause damage to the equipment; proper support for the piping and tubing; and vibration absorbers, expansion joints and rupture discs. Piping, tubing and fittings being replaced will be compatible with existing materials. Clean, adjust, service, repair and/or replace all items found to be deficient.

Wiring and Electrical Control Circuits: Check for loose, charred, broken, or damaged wiring and insulation; short circuits, loose or weak contact springs; worn or pitted contacts; proper sizing of fuses; defective operation of parts and components; and any other deficiencies. All wire splice connections will be properly insulated. All electrical wiring, splice connections, circuits, boards, and like components will be properly insulated and in accordance with the National Electrical Code (NEC) for the particular application in which used. Clean, adjust, service repair, and/or replace items found to be deficient.

Insulation: Check for wet, damaged missing and deteriorated insulation and vapor barriers; broken tie wires, loose or missing bindings and torn canvas jackets, etc. The insulation on all applicable system components shall be repaired or replaced as needed, with insulation materials having a vapor barrier and insulation value equal to or better than the original or existing materials. Insulated surfaces having moisture condensing on the surfaces shall be considered damaged and shall be replaced. Clean, adjust, service repair, and/or replace items found to be deficient.

Exhaust Air and Ventilation Systems: Check for dust, dirt, grease and oil accumulations; air flow and weather/elements integrity; suction pressures at air intake; operation of dampers, baffles, solenoids, protective guards, insect and bird screens; and caulking around flashing, ducts, collectors, smoke pipes, cowlings, hoods, caps and covers. Clean or replace filters as applicable. Check for clogging, broken or separated joints and seams in ducts, stacks, couplings, sheaves, belts, fan blades, blowers, etc. Check thermal insulation, protective coverings, vapor, barriers and loose or missing fasteners and hardware. Check for material defects and improper operation of moveable parts and components in relation to the controlling device. Check for loose, missing or poor fitting flashing, fire and safety hazards, warnings, alarms, etc. Clean, adjust, service repair, and/or replace items found to be deficient.

Valves: Check all associated valves for operation, leakage, linkages travel, range limitations, rust, dust, dirt, corrosion, scale, seizing, bending, mounting, clogging, broken, damaged or missing parts and material defects. Check source of valve operation (e.g., power pneumatic, electrical, mechanical, pneumatic/electric, etc.) for required pressures, electrical power voltages, etc. Clean, adjust, service repair, and/or replace any parts, materials, components or combinations thereof found to be deficient as a result of these inspections, and restore valve to a standard operating condition.

Cabinets, Cases, Doors, Panels, Gaskets, Latches, Handles and Hardware: Check for cracks, scrapes, gouges, separations, missing, broken or damaged parts and components, bad insulation, bad gaskets, leaks, fitting of doors, etc. Clean, adjust, service repair, and/or replace items found to be deficient.

Motors, Drives, Sheaves, Shafts, Couplings, Blowers, Fans, Hubs, Belts, Bearings, Gearboxes, Frequency Drives and Guards: Check for accumulations of dust, dirt, grease, and oil. Clean, adjust, service, repair and/or replace items as necessary to correct deficiencies such as: worn, loose, missing, or damaged parts, guards, connections and connectors, bent blades, worn, loose, broken or missing belts, unbalanced moving parts, shafts, bad bearings, ineffective isolators, vibration absorbers, etc. Check full load and run load amps of each electric motor, other than fractional H.P. motors and compare with manufacturer's data plate ratings. Check condition of motor windings, rotors, and bushings.

Thermostats, Thermometer, Pressure gauge, Sub-bases, Guards, covers, Ambient stats, Sub and Master Controllers, Sensors, Timers, Transmitters, Temperature and Pressure Controls, DDC software, etc. Check for improper settings, defective operation, calibration and cleanliness, proper input and output voltages, pneumatic air operating pressures. Check for deficiencies in wiring, tubing, piping, switches, relays, coils, solenoids, transformers, controls, sensors, thermostats and protective covers and guards, ambient stats, aqua stats, pressure switches, reversing relays, timing devices, master and sub-master controllers.

Outdoor authority override controllers, night set back settings, trending devices, etc. Clean, adjust, service repair, and/or replace items found to be deficient.

Air Handling Units (AHU), Ducts, Plenums, Stacks, Grilles, Register, Diffusers, Screens, Dampers, Vanes Mixing Boxes, VAV Boxes and Balancing of Systems: Check plenum chambers, supply and return air ducts, branch ducts, mixing boxes, VAV boxes, dampers, registers, grills, diffusers, louvers and insect/bird screens. Check for dirt, dust and trash, air leaks, broken, ripped or torn insulation and disconnected ducts, loose or broken connections, brackets,

hangers, supports and other parts, excessive vibrations or other movements, defects in metal, fiber, glass, and other materials, proper operation of movable parts such as dampers, louvers, and vanes in relation to the controlling device, and inadequate air flow and/or distribution in main and branch duct circuits. Check air handler unit systems for proper operation and correct CFM air flow. Balance air distribution systems to meet designed airflow to all areas being serviced by the systems. Check temperature and static pressures. Check turning vanes, fire dampers, access openings, doors, panels, outside air make-up systems and ducts. Clean by sweeping, brushing, dusting, vacuuming, washing, hosing with water, detergents, solvents, chemicals, air pressure, steam or other methods as are applicable to the nature of the items being cleaned and as may be required to obtain the desired results. Clean, adjust, service, repair and/or replace all items found to be deficient.

Structures, Casings, Hangers, Supports, Beams, Platforms, Slabs, Pads, Vibration Absorbers and Sound Isolators: Check mounting bolts; loose, broken or missing parts, connection and hardware; improper leveling of equipment; and defective sound cushion isolators and vibration absorbers. Check for dirt, dust, trash and other debris accumulated on or around the equipment. Check the security of all mounting and attaching points. Check for vibration and other unusual movements. Clean, adjust, service, repair and/or replace all items found to be deficient.

Compressors: Check for dust, dirt, oil and grease deposits and accumulation, leakage of refrigerant and oil, cracked/clear sight glasses and gauges, dampers fittings, piping, valves, etc. Check for loose connection, excessive or unusual noise and vibration, proper suction and discharge temperatures and pressures and indication of excessive heat. Check oil levels and unloaders for proper operation and change out dirty/contaminated oil and filters. Check compressor full load and run load amps, compare against manufacturer's data plate rating and record the findings. Check all electrical wiring and related components. Record the suction and discharge pressures and type and amount of refrigerant and oil or oil added to the system on the log sheet (as applicable) for air conditioning and compressed air compressors. Meg the motor windings on all compressor motors 15 H.P. and larger once each year and record the readings. Clean, adjust, service, repair and/or replace all items found to be deficient.

Air Cooled Condensers: Check for dust, dirt, foreign materials, oil and grease accumulation, leaks, excessive or unusual noise and vibration and loose, missing or damaged parts. Check motors, sheaves, belts, bearings, shafts, supports, brackets, hardware, etc. Check operation and calibration of fan cycling controls, low ambient switch controls and dampers, head pressure control louvers, actuators and regulators, as applicable. Check for proper airflow through the condenser coil; and bent, damaged or corroded coil fins and fan blades. Remove all weeds, bushes and other obstructions within three (3) feet of air-cooled condensers. Clean, adjust, service, repair and/or replace all items found to be deficient. Wash coil fins with water under pressure at least monthly or more often as needed. Check belt condition and tension.

Cooling Towers: Check and clean general condition of the unit & check for unusual noise or vibration. Inspect cold water basin, Flush water distribution system/inspect spray nozzles, Drain basin & piping, Inspect air inlet louvers/combined inlet shields, Check & adjust water level in basins, Check operation of make-up valve, Check & adjust bleed rate, Lubricate fan shaft bearings, Lubricate motor base adjusting screw, Check & lubricate optional gear drive, Check drive alignment, Check motor voltage & current, Clean fan motor exterior, Check fan motor for proper rotation, Inspect fan blades for cracks and clean as needed, Remove and clean strainer in sump, Change gear reducer lubricant with factory-recommended oil, Clean gear reducer sight glass and check shaft thrust and play, Power wash tower hot deck and cold deck, Power wash tower fill and use scale remover as needed, Check bottom of hot and cold decks for corrosion and rust, Check the condition of the fan motor through temperature or vibration analysis and compare to baseline values, Perform meg-ohm test motor windings, Change oil in gear box if applicable, Inspect vibration safety device.

Pump Units: Check for dust, dirt, and other foreign deposits; leaks, excessive or unusual noise and vibrations, and loose, broken or missing parts and connections. Check for correct rotation and prime. Check seals, gaskets, packing, bearings mounting base and hardware, couplings, guards, and inlet and discharge pressures and overall operations. Clean, adjust, service, repair and/or replace all items found to be deficient.

Temperature and Humidity Controls, Tending equipment: Check all control, once a month, for improper settings, loose connections, worn, dirty, pitted or misaligned contacts and any other defective parts by observing the operation through a complete cycle. Inaccuracy of thermostats may be found by comparing them with a mercury thermometer (dry-bulb type) and inaccuracy of humidistat are found by comparing them with a sling psychrometer or psychometric

chart. For problem areas identified by the QCI, the use of trending sensors will be installed and monitored to help identify the trouble. Settings will be adjusted, connections tightened, contacts cleaned, alignment adjusted, and other connections made to insure proper functioning of the system.

Replacement of Burned-Out Compressors: When compressors are replaced due to burned-out conditions, the internal refrigeration system will be thoroughly cleaned in accordance with approved and acceptable industry standards for burn-out. Additional precautions and practices will be exercised to further control refrigerant system contamination and prevent damages to replacement compressors and components. Cleanup methods will include, but are not limited to, the use of clean-up kits, suction and discharge line filters/dryers, moisture indicating sight glasses, acid testing kits, changing or adding of oil filters and system flushing, changing the oil, deep vacuuming of refrigerant system, leak checking, and any other tasks associated with the task.

Dehumidifiers: Check all electrical heating elements for burned, pitted or dirty contacts in the circuits; lubricate fanbearings, valves and linkages. Clean or change filters as needed, check for leaks and repair/replace as needed. Check desiccant levels at least yearly and replenish as necessary. Check reactivation and absorption airflow for proper operation and clean and paint as necessary.

Electric Hot Water Heaters: Check all electrical heating elements for burned, pitted or dirty contacts in the circuits paint as needed. Clean, adjust, service, repair and/or replace all items found to be deficient.

HVACR Water Treatment: The Contractor is to implement an approved testing and treatment program for HVACR Water Systems. This includes recordkeeping and report generation in the work order system (WOS). Scheduling of site visits to perform this testing and treatment, and the establishment of standards for recordkeeping and report generation, shall be approved in advance through the WOS. The Contractor shall provide additional support services for flushing, cleaning, and internal and external inspections of HVACR Water Systems at these sites as authorized by the Quality Control Plan (QCP). Removal of corrosion coupons (anodes and/or cathodes), testing, and installation of replacement coupons shall be performed by the Contractor as directed by the QCP. Regular meetings between the Contractor and the QCP, recordkeeping, and report generation/submittal are a normal part of the service herein described and will not be considered a separate billable item.

Refrigerant Recovery. The Contractor shall submit a preapproved refrigerant evacuation and storage plan to the COR by the contract start date. The refrigerant Recovery plan shall meet all environmental protection agencies Chlorofluorocarbon/Hydrochlorofluorocarbon (CFC/HCFC) Refrigerant Processing requirements. The Contractor shall keep on file all employee's universal CFC/HCFC refrigerant processing certificate. CFC/HCFC Refrigerant Processing Regulations: <https://www.epa.gov/section608/section-608-technician-certification-test-topics>

- a. The following substances have been identified as ozone depleting substances: CFC-11, CFC-12, CFC-113, CFC-114, CFC-115, Halon-1211, Halon-1301, Halon-2402, Carbon Tetrachloride, Methyl Chloroform, HCFC-22 and HCFC123.
- b. The Contractor shall identify all equipment using any of the substances identified in paragraph 3.1.2 and mark that equipment with a permanent type tag, prominently displayed, identifying the type of substance and notice of the proper procedures for working with the identified substance.
- c. The Contractor shall not allow any of the identified substances to escape into the atmosphere during any phase of maintaining, repairing, servicing, or disposing of air conditioning equipment. The Contractor shall recover/recycle all identified substances for reuse in existing equipment. All recovery equipment will be approved by the QCP prior to beginning work. The Contractor shall provide training to all individuals who deal with or service the equipment at these installations. Proof of training shall be made available to the QCP or his designated representative.

2.2.4. Emergency HVACR Maintenance. The Contractor shall respond to any emergency requests for HVACR systems within two (2) hours, twenty-four hours a day, seven days a week (24/7), and sufficiently resolve the emergency situation within one calendar day of notification. Upon stabilizing the emergency, any additional required maintenance required on HVACR systems will be further categorized as either Routine Maintenance or Non-Routine Work Requests.

Objective 2.3. Sports Fields and Playgrounds Maintenance (Objective 3)

The objective is to develop, maintain, sustain and perform a comprehensive sports field, and playground maintenance program for all areas identified in Attachment 3 in order to preserve the quality of the equipment and components to manufacturer standards through functional checks, servicing, repairing, and/or replacing.

Frequency. Frequency of the overall Maintenance objective will be established by the Preventive Maintenance Plan. The Preventive Maintenance Plan shall establish the Contractor's course of action for effectively and efficiently meeting manufacture recommendations and standards, to include frequencies for proactively performing maintenance, repairs, and replacements in order to prevent failures.

2.3.1. Performance Standard. Performance standard for services rendered under the Maintenance objective is based on adhering to the established performance frequencies. Deviation from adhering to the established performance frequencies shall result in no more than five verified complaints per month.

The tasks listed below are provided to help the contractor in gaining a better understanding of the requirements in order to successfully meet the objective. The tasks are not all inclusive as the contractor is expected to develop the total solution for meeting all the requirements of the objective in accordance with a performance-based approach.

2.3.2. Routine Sports Fields Maintenance. The objective is to inspect all sports fields monthly including, but not limited to football /soccer fields baseball diamonds, running tracks, and sand pits, recreational areas and other areas that may have athletic activities. The objective includes maintenance of these Sports Fields in order to provide a safe area to conduct athletic activities.

Tasks associated with this objective are as follows but not limited to; Sports fields are clear of debris and holes, swept, raked, and watered as necessary to sustain and promote appropriate functionality.

The objective includes performing minor work and repairs, defined as work that the Contractor will expend \$2,500.00 or less in material costs and includes inspection, periodic and preventive maintenance, operation of utilities and minor repairs incidental to schedule. Excludes damages and/or malfunctions caused by vandalism and natural disasters. Any repairs exceeding \$2,500.00 in material cost shall be identified as a non-routine work request, subject to COR's review and approval.

The Contractor shall identify, record, and take the necessary corrective action to ensure equipment and systems meet all current facility and life safety codes and record it in the Work Management System. Notify the school administration and COR of any temporary disruptions that could impact sporting activities or the educational mission and obtain written permission from the COR for any scheduled interruption.

2.3.3. Natural Grass Sports Fields Maintenance. Natural Grass Sports Fields shall be properly maintained in accordance with (IAW) manufacturer specifications, acceptable local codes, regulations and best practices, which include: Fertilization, Weed Control, over seeding, Deep Tine Aeration, Rolling, Scarifying and Sand Spreading. The COR will provide the Contractor with an annual DoDEA sport schedule and written notification 48 hours prior to required lining or athletic field mowing requirement.

- a. Maintain the grass height between 4 and 8 cm. Verticut, aeration, and watering shall be performed as necessary to maintain a healthy, green, and uniform appearance. After mowing, the height of grass shall be 4 to 5 cm. Grass clippings from the athletic fields shall not accumulate in the surface of the grass at the cut level.
- b. Remove clippings and other material from adjacent surfaces following mowing and dispose of them. Clippings on the grassed areas shall not accumulate on the surface of the grass or in windrows, bunches, or piles. Excess clippings shall be removed or mulched. Grass clippings from the first and the last grass cut of the season shall be removed from both improved and unimproved areas. During intermediate cuts,

only clippings for improved grounds shall be removed. Clippings shall be disposed of in accordance with host nation requirements.

2.3.4. Turf Field Maintenance. Turf Fields shall be vacuumed, swept, cleared of debris, weeds, treated for static electricity, and properly maintained IAW manufacturer specification to extend the life of the field and applicable warranties.

2.3.5. Sports Season Maintenance. Before the beginning of each sport season (football, soccer, softball, track andfield) sport fields shall be prepared for the appropriate sport, which may include lining, fresh sand for pits and dirt forpitching mounds. The COR must provide the Contractor with an annual DoDEA sport schedule and written notification 48 hours prior to required lining or athletic field mowing requirement.

2.3.6. Sports Field Events. As required, according to DoDEA Pacific or Pacific East District (Japan) athletic schedule, sports field/courts shall be prepared in accordance with the appropriate activity. Such activities may include, but are not limited to, field lining, relocation of bleachers, field inspections, grooming, dragging/leveling of infield materials and surface maintenance. The COR must provide written notification 48 hours prior to the scheduled event.

2.3.7. Annual Inspections and Repairs. An annual inspection report shall be submitted to COR not later than September 1st of each contract year. As a part of this inspection, the Contractor shall inspect and make minor repairs in accordance with this PWS. Items may include:

- a. Repair dugouts
- b. Repair outdoor bleachers, benches and grandstands
- c. Repair athletic field fence lines
- d. Repair basketball poles, hoops, nets and backboards
- e. Repair scoreboards, press box and public announcement (PA) systems
- f. Repair sports field/courts nets, net posts, lines, fencing, goals and surrounding structures
- g. Clean and repair running tracks with rubberized surfaces
- h. Repair climbing walls

2.3.8. Playgrounds and Playground Equipment: The objective is to inspect, maintain and repair playground equipment. Tasks associated with this objective are as follows but not limited to: perform monthly visual inspections and repair playground equipment according to Certified Playground Safety Institute or U.S. Consumer Product Safety Commission guidance, <https://www.cpsc.gov/s3fs-public/325.pdf>. Maintain the playground systems/apparatus to optimize the life, maintain operability and safety of the system/apparatus for the students. Repairs to playground equipment must meet manufactures recommendations. If there are no recommended OEM PM specifications for some or all of the equipment, the contractor shall provide a PM schedule that will be mutually agreed upon by the contractor and the COR. Maintain documentation of all inspections, maintenance, and repair of equipment for a period not less than five years.

Objective 2.4. Non-Routine Work Request (Objective 4)

Non-Routine Work Requests for HVACR Systems, Facilities, Sports Fields and Playgrounds. The Contractor shall provide non-routine repairs for DoDEA facilities listed in Attachments 1, 2 and 3 of the PWS involving electrical, mechanical, civil and structural disciplines as required and approved by the COR and Contracting Officer. Non-routine work requests are defined as work that exceeds the negotiated fixed price for recurring/routine services in material costs for repairs. In order for the contractor to perform non-routine work requests, the contractor shall submit a quote to the COR, the Contracting Officer or COR will determine if the price is fair and reasonable and will authorize work by issuing a task order or notice to proceed for the work and/or repair parts. The Government retains the right to seek solutions from other sources for fair market value. Non-routine work requests typically require more in-depth technical knowledge to correct, install, repair, or replace equipment, systems or property. The Contractor shall provide project details and the necessary labor and equipment cost estimates to complete the project. Only new standard parts of equal quality shall be used for repairs. Parts, which have been replaced, will become the property of the Government. The Contractor shall provide a disposal report of all replaced defective parts to the COR for review and approval. Replaced parts and property that are identified as a government returned asset should be provided to the COR within one week of the completed repairs unless otherwise

directed for disposal.

2.4.1. Drawings Plans and/or Specifications. In the event the nature of the work to be performed and the complexity of drawings, plans and/or specifications needed for the non-routine work requests require preparation of formal plans and/or specifications, the Contractor shall include an estimate for such work in its proposal for non-routine repair Work Order approval, and subsequently prepare the drawings, plans and/or specifications as required.

2.4.2. Material Submittals. Material submittals, if required, shall be submitted IAW the proposal and/or the resulting Task Order issued.

2.4.3. Final Inspection. All work performed shall comply with applicable Federal and local facility codes, as well as the requirements specified in the non-routine repairs Work Order. The Contractor shall conduct a final inspection of approved non-routine work requests with the COR, ACOR or any other customer representatives deemed appropriate by the Government.

2.4.4. Non-Routine Work Request for Kitchen Appliances. On as-needed basis, as required by the COR and Contracting Officer, the Contractor will install, un-install, move, remove, maintain and/or repair kitchen appliances listed in Attachments 1 and 2 of the PWS (see description below). The contractor shall provide specification sheets for all proposed new equipment to the COR prior to approval. In order to preserve appliances in a safe and serviceable condition to render proper functioning of all components. Work shall be accomplished in accordance with best commercial practices and manufacturer's specifications.

- a. Mobile Heating Cabinets
- b. Ice Machines
- c. Milk Cooler
- d. Oven Convection Dual
- e. Oven Convection Combo
- f. Oven Stove Top
- g. Refrigerator Reach-In
- h. Steamer
- i. Waste Disposal System
- j. Mobile Cold Pan Counter
- k. Mobile Frost Top Counter
- l. Steam Kettle
- m. Oven Convection Top
- n. Oven Convection Bottom
- o. Oven Combination Top
- p. Oven Combination Bottom
- q. Freezer Reach-In
- r. Can Opener Electric
- s. Buffalo Chopper
- t. Open Base Utility Counter
- u. Microwave Ovens
- v. Table Counter-Chiller
- w. Tabletop Refrigerator
- x. Display Case Pass-Thru-Cold
- y. Kettle Electric
- z. Food Processor
- aa. Food Mixer
- bb. Flat Top Counter Cold Foodcc. Cold Food Counter
- dd. Countertop Cold Food Displayee. Beverage Counter
- ff. Serving Heat Element
- gg. Tray Dispenser
- hh. Serving Carts

- ii. Cashier Counter
- jj. Customer Counter
- kk. Walk-In Freezer and Refrigerator
- ll. Insulated Hot and Cold Cabinets
- mm. Beverage /Ice Cream Cooler
- nn. Electric Range
- oo. Range Hood
- pp. Commercial Dishwasher and Soap/Rinse Agent Dispenser
- qq. Hot Water Booster
- rr. Dough Kneading Machine
- ss. Braising Pan
- tt. Commercial Food Processor
- uu. Cold Food Well Serve Line
- vv. Hot Food Well Serve Line
- ww. Countertop Refrigerated Merchandiser
- xx. Double Convection Oven Gas

2.5. General Contract Requirements.

2.5.1. Contract Management Plan. The contractor must provide management and staffing that will ensure continuity of services and establishes communication and partnering approaches between the contractor and government representatives. Therefore, the contractor must have an established management and staffing plan that covers the performance of this contract with respect to partnering, management, staffing, and recruitment and subcontractor support services. The plan, at a minimum, needs to address the following-criteria:

- a. The Contractor's approach for addressing Communication and Relationship Management.
- b. DoDEA utilizes a commercial off- the-shelf (COTS) program – Workload Management System called School Dude to track work orders, manage customer requests, and improve workflow. Offerors will be required to utilize this work order system to respond and manage work order requests. Access will be provided through DoDEA Contracting Officer Representatives (CORs).
- c. A process for managing School Dude. Contractor will ensure they have capabilities for reliable Internet connectivity between contractor employees and Government representatives to ensure maximum use of School Dude. Access to School Dude and School Dude on-line training (approximately 2 hours) shall be provided at no cost to the Contractor.
- d. A process for managing the recruitment hiring, retention, substitution and replacement of qualified personnel, and how proposed staffing levels will be maintained throughout the life of the contract.
- e. Identification of key personnel and provide a detailed approach to coordination and interface with the Government, internal company hierarchy and supervision, and operational control and oversight of personnel including subcontractors, if applicable.
- f. How an initiative of this magnitude and complexity will be managed and administered from the top down, what processes will be in place to ensure effective and unabated communications between all stakeholders, and what procedural standardization is in effect to ensure timely resolution of problematic areas.
- g. Procedures for obtaining clearances for installation access; an approach for a viable reach-back capability for surge contingency; limitation of manpower turnover rate; work scheduling and status reporting procedures; and processes or control measures to ensure effective status reporting and overall continuity of services.
- h. A management approach to transitions as turnover occurs to ensure there is a timely and transparent transfer

of knowledge between Contractor and Government personnel; resolving issues and conflict at the lowest possible levels in a timely manner without impact to school operations; what internal and external communication processes are in place with respect to all aspects of contract performance; what oversight will be in place to ensure contract personnel comply with standard operating procedures while simultaneously maintaining a high degree of professionalism; what the procedures are for placing, overseeing, and maintaining quality subcontractor personnel; and the methods of mitigating and monitoring risk of performance to meet or exceed all requirements in the PWS.

- i. A process detailing how the Contractor will respond to service calls in a timely manner.
- j. A plan detailing how the Contractor will use technology or other approved methods to communicate with DoDEA to receive and respond to service calls, emergencies, etc.
- k. Contingency Plan for separation of employees and employee absences IAW 2.5.1.d.

2.5.2. Preventive Maintenance Plan. Preventive Maintenance Plan shall establish the Contractor's course of action for effectively and efficiently meeting manufacture recommendations and standards, to include frequencies for proactively performing maintenance, repairs, and replacements in order to prevent failures. The plan shall also include a process for:

- a. Tracing system and equipment malfunctions to the cause and taking the corrective action as required. The Contractor shall identify, record, and take the necessary corrective action to ensure equipment and systems meet all current facility and life safety codes and record it in the Work Management System (School Dude).
- b. The coordination of causes identified as being outside/not within DoDEA Pacific jurisdiction or control, which will need to be coordinated with the installation or local Public Works Department to ensure the problem is corrected. The Contractor shall establish a process for notifying the school administration and COR of any temporary disruptions in service that could impact the educational mission and obtain written permission from the COR for any scheduled utility interruption.

2.5.3. Quality Control Plan (QCP). QCP shall establish the contractor's system for controlling quality of performance to ensure quality services are provided to the government in accordance with the contract's terms and conditions. The Contractor shall develop and maintain a QCP and any updates/changes, shall be submitted to COR and Contracting Officer within 10 days of incorporation of any changes into the Plan. QCP will be reviewed annually with COR at the beginning of the new contract period to validate effectiveness and update as necessary.

2.5.4. Transition.

This objective requires the Contractor to develop, submit and implement comprehensive procedures to ensure the seamless transition to the level of service prescribed and within the time allowed under the terms of the contract during the transition-in/transition-out periods. To minimize any decreases in productivity and to prevent possible negative impacts on additional services, the Contractor shall have personnel on board during the required transition-in/transition-out period(s). The transition period will be thirty (30) days.

2.5.4.1. Transition-In. "Transition-in" consists of the period of time between contract award and the start date of operational performance. During the transition-in period, the Contractor shall become familiar with performance requirements in order to commence full performance of services at the beginning of the first period of performance under this contract. The Contractor's management personnel will be permitted to observe any on-going operations as approved by the COR.

During the transition-in, the Contractor at a minimum shall:

- a. Establish a Contractor's project management point of contact to coordinate transition-in tasks with the Government

- b. Provide updates to the Transition-In Plan proposed in response to the solicitation within ten (10) businessdays after contract award
- c. Recruit and hire necessary personnel
- d. Obtain all required certification and clearances, including personnel security clearances and badging
- e. Attend post-award meetings as required
- f. Work with the current Contractor for facility turnover
- g. Accomplish School Dude Training
- h. The contractor shall update facility systems inventories such as HVACR equipment list, etc. Establish services and provide addresses and phone numbers to KO and COR forty-five (45) calendar days after award. This includes providing a roster with emergency contact numbers of key personnel. The Contractor shall also provide the Government key personnel information for each facility. Updates of this information shall be provided to the COR and KO through the life of the contract.

2.5.4.2. Transition-Out. “Transition-out” consists of the period of time between award of a follow-on contract to a different contractor and the final date of operational performance under the current contract. During the transition-out, the Contractor shall continue to provide all services, provide full access to Government facilities and equipment (if any) to the incoming Contractor and take all actions necessary to smoothly transition from the current contract.

During the transition-out, the Contractor at a minimum shall:

- a. Establish a Contractor’s project management point of contact to coordinate transition-out tasks with theGovernment
- b. Provide a Transition-Out Plan no less than thirty (30) days prior to the start of the transition-out period
- c. Provide necessary documentation and information to incoming Contractor on the facilities, grounds, etc.
- d. Provide facility handoff, key control and any security issues. All keys are required to be turned over within3 business days of completion of the previous contract
- e. Turn in base access passes to installation Pass and Registration Office as required
- f. Retain staff devoted to each task or activity and time allocation for each to ensure that sufficient, qualifiedand properly trained personnel are available to accomplish all contractual requirements until the end of the transition-out.

2.5.5. Reporting Requirement.

2.5.5.1. Contractor Monthly Status Report. This objective requires the Contractor to provide a monthly report forall maintenance work orders accomplished and pending work orders, which includes non-routine work requests. Thisreport shall be submitted to the appointed COR via e-mail IAW the table located in section 5 of this PWS.

2.5.5.2. Service Contract Reporting Procedures. The Contractor shall report ALL contractor labor hours (including subcontractor labor hours) required for performance of services provided under this contract for the Pacific East District (Japan) Building and Sports Field Maintenance and Services Contract via a secure data collection site, IAW the table located in section 5 of this PWS.

3. Constraints.

3.1. Hours of Operation. Services shall be provided during normal hours of school operation which are 0700 to1630 Monday through Friday, except U.S. Federal holidays. Services may also be provided at such other times as required by the nature of the work, such as before and after school hours and summer events and/or on Saturdays and Sundays. This is at the discretion of the contractor, and at no additional cost to the Government, though it is to be coordinated with and approved by the COR.

The following is a list of US Federal Holidays applicable to this contract:

January 1	New Year's Day
Third Monday in January	Martin Luther King, Jr. Birthday

Third Monday in February	President's Day
Last Monday in May	Memorial Day
June 19	National Independence Day
July 4	Independence Day
First Monday in September	Labor Day
Second Monday in October	Columbus Day
November 11	Veterans Day
Fourth Thursday in November	Thanksgiving Day
December 25	Christmas Day

3.1.1. Typhoon Conditions. Contractor employees shall be excused from maintenance duties upon the declaration of Tropical Cyclone Condition of Readiness (TCCOR) 1-Caution (1C). Contractor employees need to be available to return to work upon declaration of TCCOR Recovery. Contractor employees shall return to their normal tasks upon the declaration of TCCOR Storm Watch (SW) or All Clear, which will include debris removal caused by the inclement weather to ensure facilities are safe to operate as scheduled.

3.2. Personnel. The Contractor shall provide adequate numbers of qualified personnel to assure quality performance of the services required by this contract. Furthermore, the Contractor shall provide all necessary management, oversight, direction and supervision for all work under the contract, to include all matters pertaining to work identification, performance of services and delivery of data, employee hiring, orientation and training, utilization, payment and administration, purchasing and subcontracts and establishment and maintenance of records. All on-site supervisors shall have the ability to read, write and speak the English language at a level of fluency that allows for clear communication.

3.2.1. Program Manager. The Contractor shall provide at minimum, a Program Manager dedicated to this contract who acts as the overall manager and central point of contact with the Government for work performed under this contract. The PM shall be fluent in writing, reading, speaking, and understanding the English language and shall be fully capable of conducting in-depth technical and non-technical conversations concerning their work and be able to convey those technical and non-technical discussions into easily understandable and grammatically correct written documentation. Another individual or individuals shall be designated to act for the PM in his/her absence. Notification of such designation shall be furnished to the Government.

The PM or designated alternate shall have full authority to commit the Contractor to immediate action on matters pertaining to the administration of this contract. At a minimum, the PM shall possess a cell phone and email address for communication with Government personnel during normal business hours. Furthermore, the PM shall be available to communicate with the Government outside of normal business hours for emergency purposes.

3.2.2. Key Personnel. The PM and other proposed key personnel are considered essential to the work being performed under this contract. Before removing, replacing, or diverting any of the listed or specified personnel, the Contractor must: (1) Notify the Contracting Officer and the COR within (3) three business days; (2) submit justification (including proposed substitutions) in sufficient detail to permit evaluation of the impact on this contract; and (3) obtain the Contracting Officer's written approval. Notwithstanding the foregoing, if the Contractor deems immediate removal or suspension of any member of its management team is necessary to fulfill its obligation to maintain satisfactory standards of employee competency, conduct, and integrity the Contractor may remove or suspend such person at once, although the Contractor must notify Contracting Officer and the COR prior to or concurrently with such action.

3.2.3. Personnel List. Ten days after contract award and within ten business days of updates to the Personnel List, the Contractor shall provide a list of all personnel to perform services under this contract. The Contractor shall identify points of contacts for each school/region for duty and non-duty hours. The list shall include personnel name, telephone number, email address and assigned work area.

Furthermore, the Personnel List shall include an Emergency Contact Roster including home telephone number of key emergency and on-call personnel to the DoDEA Facilities Division, local DSO, COR and KO.

3.2.4. Employee Conduct and Appearance. The Contractor shall provide professional and responsive service that:

- a. Delivers high quality and responsive service to every customer
- b. Projects positive attitude and proactive assistance
- c. Treats everyone with courtesy and respect
- d. Honors commitments and agreed upon deadlines
- e. Perform work in a manner that does not disturb students, faculty or other facility occupants

During performance of this contract while in government (School and Office) facilities, Contractor employees shall NOT under any circumstances:

- a. Use verbal assault, foul language, personal or racial insults, or threats of personal violence, or comment on the personal appearance of students and government employees
- b. Engage in any conduct of a sexual nature, verbal or physical, to include reading or display of nudity or pornographic material
- c. Engage in physical contact with students and government employees, except as required for reasons of safety, first aid, or CPR
- d. Show verbal or physical affection toward students or government employees, or take photographs of them
- e. Report for work under the influence of or impaired by alcohol, drugs, or medications which may affect the ability to perform safely under this contract
- f. Sell, give to, or accept from students any beverage, food or tobacco product, or any gift or item, irrespective of monetary value
- g. Wear clothing with insignia reflecting religious, political or social messages or slogans, but shall dress in a neat, professional manner

Contractor personnel shall dress appropriately, present a professional appearance and be well groomed for the duties being performed in a pre-kindergarten through 12th grade school environment as well as office environment (shorts, T-shirts, sandals, etc. are examples of dress that is not appropriate). Contractor personnel (other than Program Manager) shall be furnished with uniforms bearing a company patch or logo, and a badge. Smoking is allowed only in designated smoking areas and out of sight or smell of any DoDEA students (typically only outside the school fence line).

The Contractor shall safeguard and maintain all Government property as well as provide for the safety and well-being of personnel employed in the performance of this contract. The Contracting Officer may require the Contractor to remove from any facility or grounds any employee working under this contract for reasons of misconduct, safety or security at any time during the life of the contract. Any Contractor employees found working under the influence of alcohol, drugs or other incapacitating agents shall be removed and replaced by Contractor. The Contractor shall immediately inform the KO when it is learned that an employee performing under this contract has been arrested for a criminal offense.

3.2.5. Certification & Training Requirements. All Contractor personnel are required to maintain up-to-date certifications and adhere to all recertification requirements. The Contractor shall maintain records of all orientation and training provided and all documentation herein (i.e., certification letters) shall be verifiable by the Government upon request. In the event of new training requirements pertaining to the performance of this PWS, the Contractor is responsible for providing training to contracted personnel on the new requirements, as appropriate.

3.2.5.1. General.

- a. The Contractor shall provide initial orientation and quality system training to all new employees prior to assignment of employees to work under the contract.
- b. Provide follow-on quality system and other training as required during contract performance.

3.2.5.2. Specialized

- a. Asbestos Training: The Contractor shall ensure that, at a minimum, two (2) supervisory employees (one primary and one alternate) successfully complete and maintain the Asbestos Hazard Emergency Response Act (AHERA) 40-hour supervisor's training and annual 8-hour refresher course. Names and training certificates shall be provided to COR at commencement of contract performance. Ensure all other employees receive Asbestos Containing Material (ACM) Awareness 2-hour training annually. Maintain training completion records of all ACM Awareness training. Copies of training certificates for each employee must be provided to the COR by 30 August of each calendar year and before any new employee can commence work at any DoDEA facility.
- b. Hazardous Material and Waste Management Orientation: The Contractor shall ensure that all contract employees are properly briefed on how to recognize potentially hazardous materials and/or waste, including ACM, as well as who to notify in the event suspected hazardous material and/or waste is discovered and first-response measures that may be taken. Each installation has specific requirements and provides the orientation. This shall be completed within 60 days after contract award.
- c. The contractor shall have sufficient staffing with technical experience and certified craftsmen to meet the requirements outlined in this PWS, which includes:
 - 1) HVACR Operation and Maintenance Class 1 Certification
 - 2) HVACR Technical Repairs and Troubleshooting Class 2 Certification
 - 3) Refrigerant Gas Recovery Certification
 - 4) Gas Pipe Welding Class 2 Certification
 - 5) Electrical Troubleshooting Class 2 Certification
 - 6) Structural Licensing Class 2 Certification in Steel, Concrete and Wood
 - 7) Plumbing Licensing Class 2 Certification in utilities, piping, sewer and water treatment

3.2.6. Licenses/Insurance. Contractor-owned and operated vehicles shall have the appropriate registration and insurance IAW installation requirements. Contractor employees shall possess a valid Japanese license and/or applicable license issued by the installation for specialized vehicles.

3.3. Key Control. The Contractor shall restrict use of U.S. Government keys in the custody of the Contractor to contract employees and other specifically authorized personnel. The Contractor shall ensure employees maintain proper control of keys to DoDEA facilities. No keys issued to the Contractor shall be duplicated. If keys are lost, stolen or misplaced by Contractor personnel, the Contractor shall notify the COR immediately. The Contractor may be held responsible for replacing affected locks. School related keys issued to contract personnel will not be transferred onto anyone else without prior written approval by school key custodian.

3.3.1. Access to Locked Areas. Restrict use of U.S. Government keys in the custody of Contractor to contract employees and other specifically authorized personnel approved by the COR. Do not open locked areas permitting entrance by other personnel unless authorized by Contractor management, the COR, or other authorized representative of DoDEA.

3.4. Damage. The Contractor shall be held liable to the Government for any damages to the Government facility, grounds, fixtures, furnishings, or equipment to include vehicles caused by the Contractor. The Contractor shall restore, repair or replace any damage caused by Contractor operations, including the replacement of any plant materials damaged as a result of negligence at no cost to the Government.

3.5. Security Requirements.

3.5.1. Installation/Base Passes and Access. The local supporting military installation will issue all required installation/base passes to contractor employees at no cost to the Contractor. To be eligible to perform work under this contract, the Contractor must meet all applicable Pacific-Japan installation/base access requirements covered including USFJ 31-204, Restrictions on Designated Third Country Nationals to USFJ Installation and Areas. Passes must be in the employee's possession at all times while on a military installation. The Contractor shall return base passes to the appropriate office within one (1) business day upon termination of employment or completion of this contract.

The Contractor shall ensure that they coordinate Installation/Base Passes Access well in advance of the projected start dates for their employees as the turnaround is unpredictable and can vary for different locations. The COR will provide the specific document and submission deadlines for each installation upon award of the contract.

3.5.2. Visitor Policies. The Contractor shall ensure all contracted employees strictly comply with established DoDEA visitor policies pursuant to DoDEA Instruction 5205.02, Force Protection Program, which can be provided by the COR upon request. This includes the mandatory use of visitor badges necessitating the positive identification of all visitors and Contractors. Visitor or Contractor non-compliance with the visitor policy will be documented within 24 hours of occurrence for follow-up with the Contracting Officer or Installation Commander, as appropriate.

3.5.3. Security. The contractor shall not disclose or cause to be disseminated any information concerning the operation of the US bases or schools which could result in, or which could increase the likelihood of the possibility of a breach of base security or interrupt the continuity of their operations. The COR shall be notified within 24 hours of occurrence of all inquiries in connection to the performance of this contract which may cause or require the dissemination of official information. All Contractor employees performing under this contract shall be required to adhere to the provisions outlined under DoD Regulation 5400.11, DoD Privacy and Civil Liberties Programs. All Contractor personnel shall be required to sign in daily at the visitor's log in each school where work is performed during school hours and wear the appropriate visitor's badge. The signing in of Contractor personnel is for the safety and security of the school.

The Contractor shall be responsible for properly safeguarding all government property and shall not leave exterior doors propped open during the course of their duties, especially after school hours. Contractor personnel will not open exterior doors for visitors during the course of their duties. Exterior doors will remain closed and secured at all times.

3.6. Safety Requirements. The Contractor shall comply with all Japan and U.S. military facility/base safety protection and environmental conservation program requirements. The Contractor shall provide all necessary safety equipment, signs, lights, and barricades. The Contractor shall ensure contractor personnel are trained on the proper use of all chemicals and equipment so they can be used safely.

3.6.1. Safety Violations. The Contractor shall report all accidents and/or safety violations to the COR and Contracting Officer within 24 hours of occurrence followed up by providing a written report within 72 hours from the occurrence to the COR and Contracting Officer.

3.6.2. Fire Prevention. The Contractor shall comply with military facility/base fire prevention and protection requirements and ensure their personnel are trained on fire prevention procedures. The training shall include as a minimum: (1) use and location of fire alarms and fire extinguishers; (2) storage and use of combustible materials; (3) required fire protection devices while using contractor furnished equipment, chemicals, etc.; and (4) procedures when a fire alarm has been activated.

3.6.3. Medical. The Government is not liable for any medical treatment of on-the-job injuries. The Contractor shall be responsible for obtaining medical assistance for his personnel for all job-related injuries. Should the Contractor's employees use, or Contractor request the use of a medical treatment facility for emergency, life-threatening on-the-job injuries, the contractor shall be responsible for payment to the medical treatment facility for all services rendered.

3.6.4. Chemicals/Solutions. The contractor shall comply with DoDI 6050.05, (DOD HAZARD COMMUNICATION (HAZCOM) PROGRAM), 29 CFR 1910.1200; OSHA Hazard Communication Standards (HCS). Only materials, chemicals, and solutions approved and registered in accordance with the Environmental Protection Agency (EPA) guidelines and/or Japanese Environmental Governing Standards (JEGS) will be utilized. Established labeling standards will conform to the United Nations Global Harmonized System of Classification and Labeling of Chemicals (GHS) and Safety Data Sheets (SDSs) standards.

3.6.5. Labeling. Chemical and solution labels will conform to below Hazard Communication Standards format. (See Attachment 1 – OSHA BRIEF HAZCOM Standard: Labels and Pictograms)

- a. Signal Word. Used to indicate the relative level of severity of hazard and alert the reader to a potential hazard on the label. There are only two signal words, “Danger” and “Warning.” Within a specific hazard class, “Danger” is used for the more severe hazards and “Warning” is used for the less severe hazards.
- b. Pictogram. Occupational Safety and Health Administration’s (OSHA) required pictograms must be in the shape of a square set at a point and include a black hazard symbol on a white background with a red frame sufficiently wide enough to be clearly visible. A square red frame set at a point without a hazard symbol is not a pictogram and is not permitted on the label. OSHA has designated eight pictograms under this standard for application to a hazard category. (See Attachment 2).
- c. Hazard Statement. Describe the nature of the hazard(s) of a chemical, including, where appropriate, the degree of hazard. For example: “Causes damage to kidneys through prolonged or repeated exposure when absorbed through the skin.” All of the applicable hazard statements must appear on the label.
- d. Precautionary Statement(s). Provide a phrase that describes recommended measures that should be taken to minimize or prevent adverse effects resulting from exposure to a hazardous chemical or improper storage or handling.
- e. Name, address and phone number of the chemical manufacturer, distributor, or importer.

3.6.6. Safety Data Sheets (SDS). The Safety Data Sheets (SDS) should be in the following format (See Attachment 2 – OSHA SDS Literature.).

- a. Section 1. Identification
- b. Section 2. Hazard(s) identification
- c. Section 3. Composition/information on ingredients
- d. Section 4. First-Aid measures
- e. Section 5. Fire-fighting measures
- f. Section 6. Accidental release measures
- g. Section 7. Handling and storage
- h. Section 8. Exposure controls/personal protection
- i. Section 9. Physical and chemical properties
- j. Section 10. Stability and reactivity
- k. Section 11. Toxicological information
- l. Section 12. Ecological information
- m. Section 13. Disposal considerations
- n. Section 14. Transport information
- o. Section 15. Regulatory information
- p. Section 16. Other information, including date of preparation or last revision

All containers of cleaning chemicals/solutions shall be labeled in English according to 3.6.5 of this PWS. All containers of cleaning chemicals/solutions shall be closely monitored when in use and secured in applicable cabinets/lockers when not in use. Contractors are to ensure that after work is completed all areas are cleaned and all hazardous chemicals are removed from the worksite. Contractors are responsible for the safe disposition of all hazardous chemicals and decontamination of workspaces.

3.6.7. Service Interruptions. The contractor shall notify the COR of any scheduled interruptions at least 1 week in advance. The Contractor shall notify the COR as soon as possible whenever there is an unscheduled interruption or discontinuance of normal facilities services. If the discontinued service is due to any emergency breakdown, the Contractor shall notify the COR and Contracting Officer, affected tenants, and customers within thirty (30) minutes.

4. Government/Contractor Furnished Resources

4.1. Government Furnished Property

- a. Facility Access. The Government will provide access to all facilities in performance of the services outlined in this PWS and contractor's approved Work Plan for each specific site. Access other than the preceding will be provided on an as needed basis approved by the COR or Contracting Officer.
- b. Utility Availability. The Government furnishes utilities in Government-owned facilities at no cost. The Contractor shall use utilities in a prudent manner consistent with energy conservation policies. Use lights only where work is being performed. Turn off water faucets at end of use. The Contractor shall be responsible for providing necessary service lines from existing government outlets to the work site.
- c. Government Furnished Materials (GFM). The Contractor shall provide all tools, equipment and supplies to accomplish the contract requirements of this PWS. During the duration of this contract, the Government may provide already available GFM for temporary use. Upon receipt of any available GFM, the Contractor shall inventory, sign for receipt, maintain and return it in the same condition it was provided or replace it with a similar item of quality and condition as determined by the COR.

4.2. Tools, Equipment and Supplies

- a. Tools, Equipment and Supplies. The Contractor shall provide all tools, equipment and supplies to accomplish the contract requirements. All equipment shall be used IAW manufacturer recommendations. The Contractor shall use electrical equipment that meets all safety requirements and operates using existing building circuits.
- b. Materials and Supplies. Materials and supplies not furnished by the Government in support of the contract requirements shall meet all safety and health requirements/standards for use in areas and facilities where humans or animals are present. All chemicals shall have Safety Data Sheets posted and readily available wherever the chemicals are being stored and/or utilized. It is the Contractor's responsibility to secure the work area at the end of each day.

5. Contract Deliverables. Timely deliverables are important to the success of the contract. Timely is defined as the deliverables being received by all parties by the due date referenced in the Deliverables Schedule. For e-mail deliverable submissions, the received date is the date the deliverable is e-mailed by the Contractor to the recipient(s).

Deliverables Schedule						
Deliverable	PWS Reference	Frequency	Number of Copies	Medium/Format	Responsible Party	Submit To
Contract Management Plan	2.5.1	Thirty calendar days after contract award and within ten calendar days of any changes as approved by the COR.	1	Email Office 365 product or earlier compatible versions.	Contractor	COR
Preventive Maintenance Plan	2.5.2	Thirty calendar days after contract award and within ten calendar days of any changes.	1	Email Office 365 product or earlier compatible versions.	Contractor	COR

Quality Control Plan	2.5.3	Thirty calendar days after contract award and within ten calendar days of any changes.	1	Email Office 365 product or earlier compatible versions.	Contractor	COR
Transition-In Plan	2.5.4.1	Ten calendar days after contract award.	1	Email Office 365 product or earlier compatible versions.	Contractor	COR
Hazardous Material and Waste Management Training	3.2.5.1	Within thirty calendar days after contract award. The certification shall be reported to the Government within two calendar days after completion of the training, prior to a new employee commencing work at any DoDEA facility.	1	Email Office 365 product or earlier compatible versions.	Contractor	COR
Asbestos Training Records	3.2.5.1	By 30 August of each calendar year and before a new employee commencing work at any DoDEA facility	1	Email Office 365 product or earlier compatible versions.	Contractor	COR
Contractor Monthly Status Report	2.5.5.1	No later than the 10th day of each month.	1	Email Office 365 product or earlier compatible versions.	Contractor	COR
Security Inquiries	3.5	Within 24 hours of occurrence.	1	Email Office 365 product or earlier compatible versions.	Contractor	COR
Safety Data Reports	3.6	Ten calendar days prior to the first day of the contract period of performance and within two business days before the introductions of any new chemicals.	1	Email Office 365 product or earlier compatible versions.	Contractor	COR

6. Acronyms & Definitions of Terms

6.1. Acronyms

AAFES – Army and Air Force Exchange Service
ACM – Asbestos Containing Material
BCE – Base Civil Engineer (US Air Force)
CFR – U.S. Code of Federal Regulations
COR – Contracting Officer's Representative
CPSC – U.S. Consumer Product Safety Commission
DPW – Department of Public Works (Army)
DSO – District Superintendent's Office
FAR – U.S. Federal Acquisition Regulation
GFCI – Ground Fault Circuit Interrupter
GFE – Government-furnished equipment
FTE – Full Time Employee
GFP – Government-furnished property

HEPA – High Efficiency Particulate Arresting
 HVACR – Heating, Ventilating, Air Conditioning and Refrigeration
 IAW – In Accordance With
 IDIQ – Indefinite Delivery / Indefinite Quantity
 KO – U.S. Government Contracting Officer NEC – U.S. National Electric Code
 NFPA – U.S. National Fire Protection Association NTP – Notice to Proceed
 OEM – Original Equipment Manufacturer PAP – Performance Assessment Plan
 PM – Preventive Maintenance
 PW – Public Works (Marine Corps FE or Air Force BCE) PWS – Performance Work Statement
 RCMP – Reliability Centered Maintenance Program
 RFP – Request for Proposal
 RFQ – Request for Quotation RM – Routine Maintenance
 SCR – Service Contract Reporting SF – Square Foot
 TO – Task Order
 Work Management System - Schooldude.com or other automated tracking system WO – Work Order(s)

6.2. Definitions of Terms

Addition. A change to a real property facility that adds to its overall external dimension or footprint.

Alteration. A change to interior or exterior facility arrangements or components to improve current use. This includes installed equipment made a part of an existing facility. Additions, expansions or extensions are not alterations.

Asbestos Hazard Abatement. Activity is defined as any activity involving the removal, renovation, enclosure, repair or encapsulation of any asbestos containing materials in any amount.

Breakdown: The stoppage or collapse of equipment, of a facility, or a component thereof, which requires immediate corrective action to restore it to an operating condition.

Contract Discrepancy Report (CDR). A formal, written documentation of contractor poor performance or lack of performance for contracted work.

Contract Employee. Any prime or subcontractor employee assigned full time or regular part time to this contract.

Contracting Officer (KO). The individual with the authority to enter into, administer, and/or terminate contracts. The Contracting Officer is the exclusive Government official authorized to execute changes and authorize deviations or variations from this contract.

Contracting Officer's Representative (COR). An authorized designee of the Contracting Officer.

Critical Equipment and Facilities. Equipment or facilities that must operate continuously or throughout the respective season in order to support school operations. Failure of equipment or facilities to meet design output requirements may affect the health and welfare of personnel or damage Government equipment or properties. Emergency or urgent services calls are often required to restore critical equipment to optimum operating condition and provide the output required, e.g., fire prevention and protection systems, electrical systems, and utility systems, etc.

Department of Defense Education Activity Pacific (DoDEA Pacific). The Area Headquarters for DoDEA schools within the Pacific.

District Superintendent's Office (DSO). The District Headquarters responsible for the operations of all schools located within their respective District. District Offices are charged with providing the professional architectural and engineering services required to manage the maintenance, repair, and improvements of all District school facilities.

Emergency Work/Emergency Maintenance. Work required during or after normal duty hours to correct an emergency situation that threatens health, safety, property, or mission. An emergency includes, but is not limited to, utility failure, ~~elevator failure~~, fire hazards, environmental hazards, air conditioning failure, broken locks, broken windows, broken water lines, or sewer backups. It also includes elimination of fire, health, or safety hazards, or any other hazard deemed detrimental to the mission or operational effectiveness.

Equipment-in-Place (EIP). EIP is a special category of personal property. It consists of capital equipment and other nonexpendable supplies of a movable nature that are not affixed as an integral part of the facility and may be removed without destroying or reducing the usefulness of the facility.

Facilities. Any interest in land, structures or complex of structures, supporting road and utility improvements necessary to support the functions of an activity or mission.

Inspection. Procedures for the evaluation and determination of the actual condition of facilities, mechanical operation and technical components of systems are operating IAW manufacturer specifications and intended use.

Installed Equipment. Equipment and furnishings required to make the facility usable and attached as a permanent part of the structure.

Major Components. Roof structures, exterior walls, interior walls, heating systems, plumbing systems, chimneys, stairwells, interior and exterior caulking, interior ceiling tiles, floor coverings, wall covering, duct insulation, electrical service panels, transformers, exterior landscaping, site grading.

Major Equipment. A piece of equipment that is separate and distinct as well as critical and necessary to a system's functioning. An example of major equipment related to Heating Ventilation and Air Conditioning.

Personal Property. Any property not considered real property. This includes property book items.

Performance Assessment: Those actions taken by the Government to assure services meet the requirements of the performance work statement (PWS).

Performance Assessment Plan (PAP). A written Government plan detailing how Contractor performance and Quality Control will be monitored and assessed by the Government to ensure receipt of quality services and facilitate payment in accordance with the contract's terms and conditions.

Non-Routine Work Request or Project Repairs. Project Repairs are a form of Work Order that requires more in-depth technical knowledge to correct, repair or replace equipment, systems or property. Contractor will provide project details and the necessary labor and equipment cost estimates to complete the project.

Quality Control Plan (QCP). The contractor's system for controlling quality of performance to ensure quality services are provided to the government in accordance with the contract's terms and conditions.

Real Property. All land and interest in lands. Includes buildings, warehouses, right-of-way, basements, utility systems, and all other improvements permanently attached and ordinarily regarded as real estate. Does not include machinery, equipment, or fixed signal communication systems that may be removed without harming the usefulness of the structure.

Repair. The application of maintenance services or other maintenance action to restore serviceability to an item by correcting specific damage, fault, malfunction, or failure in a part, subassembly, module (component or assembly), end item, or system.

Repair Parts and Materials. Parts, materials, supplies, and equipment provided by the Contractor to support all routine maintenance, sustainment, and minor construction services.

Response. To have personnel on site at the school facility pursuing a solution to the stated problem.

Routine Maintenance. Maintenance of buildings and all outlying physical appurtenances as defined in this PWS. Frequencies stated are minimum frequencies unless manufactures recommendations or industry standards dictate a more frequent interval between inspections, at which case the more frequent interval shall be followed.

Supplies and Materials. Materials, supplies, and equipment provided by the Contractor to support all routine services.

Sustainment. Repair services necessary to ensure optimal condition of facility components and operations over its life-cycle duration. Such work includes the full spectrum of immediate or scheduled repair and or replacement services and any services to be provided on an emergency basis.

Urgent. Work required during normal duty hours to correct a situation that threatens health, safety, property, or mission. Urgent work includes, but is not limited to; utility failure, fire hazards, environmental hazards, fire alarm system failure, heating failure, broken locks, broken windows, broken water lines, or sewer backups. It also includes elimination of fire, health, or safety hazards, or any other hazard deemed detrimental to the mission or operational effectiveness.

Work Management System (WMS). The Work Managements System currently utilized by the Pacific East District (District) is School Dude at: <https://login.schooldude.com>. As required by DoDEA or District leadership, the WMS will be utilized to track all work order requests, provide the necessary feedback to the customer on work order status, track customer feedback, provide documented estimates for Repair Projects and provide work order reports.

Work Order/Work Request (WO). A work order is a request for general labor support facility maintenance, HVACR maintenance, sport field & playground maintenance and project repairs or non-routine work requests.

6.3 Applicable Documents. The following United States Department of Labor Occupational Safety and Health Administration regulations or equivalent host nation regulations, whichever are more stringent, are applicable to this document:

29 CFR 1910.1200; OSHA Hazard Communication Standards (HCS)
<https://www.osha.gov/dsg/hazcom/standards.html>

7. Performance Requirement Summary (PRS). The following summarizes all the objectives of the requirement along with the performance standards and Acceptable Quality Levels (AQL).

Performance Objective	Performance Standard	AQL	Inspection Method
Facility Maintenance	All tasks completed in accordance with frequency and standard stated in PWS section 2.1.	No more than five verified complaints per month.	Periodic Surveillance, Monthly StatusReports and Work Management System.
Heating, Ventilating and Air Conditioning (HVACR) Maintenance	All tasks completed in accordance with frequency and standard stated in PWS section 2.2.	No more than five verified complaints per month.	Periodic Surveillance, Monthly StatusReports and Work Management System.

Sports Fields and Playgrounds Maintenance	All tasks completed in accordance with frequency and standard stated in PWS section 2.3.	No more than five verified complaints per month.	Periodic Surveillance, Monthly Status Reports and Work Management System.
Non-Routine Work Requests	All tasks completed in accordance with the standard stated in PWS section 2.4.	No more than five verified complaints per month.	Periodic Surveillance, Monthly Status Reports and Work Management System.

*Note: Work Management System/School Dude will be utilized to track all deficiencies noted during routine facility inspections, track work requests, and provide status and reports.

7.1. Quality Assurance Surveillance Plan (QASP). The Government will utilize a QASP to monitor the contractor's performance on the contract. The QASP is a living document and can change at any time during the life of the contract. As such, the Government reserves the right to unilaterally edit the QASP at the Government's discretion.

8. List of Attachments

Attachment 1: Equipment List for Each School
Attachment 2: School Component List for Each School
Attachment 3: School Play Area List for Each School
Attachment 4: Quality Assurance and Surveillance Plan

(End of PWS)

Appendix A
Service Locations

1. Camp Zama
 - a. Zama Middle/High School
 - b. Student Transportation Office
2. Misawa Air Base
 - a. Edgren Middle/High School
 - b. Sollars Elementary School
 - c. Student Transportation Office
3. Sagami Depot
 - a. District Warehouse
4. Sagamihara Family Housing Area
5. Arnn Elementary School
6. Yokota Air Base
 - a. District Superintendent's Office
 - b. Mendel Elementary School
 - c. Yokota High School
 - d. Yokota Middle School
 - e. Yokota West Elementary School

Appendix B
Approximate Facility Population

Location	Students	Staff	Total
Arnn Elementary School	288	53	341
District Superintendent's Office	0	68	68
Edgren Middle/High School	373	67	440
Mendel Elementary School	521	97	618
Sollars Elementary School	514	88	602
Student Transportation Office Camp Zama	0	15	15
Student Transportation Office Misawa Air Base	0	15	15
Student Transportation Office Yokota Air Base	0	33	33
Yokota High School	282	50	332
Yokota Middle School	266	44	310
Yokota West Elementary School	147	41	188
Zama Middle/High School	516	73	589
Total	2,907	644	3,551

Appendix C
Building Numbers and Area

Facility	Building Number	Area (Square Feet)
Arnn Elementary School	12201, 12202, 12203	102,052
District Superintendent's Office	1240, 1378, 1584, 4159	21,194
District Warehouse	17210	3,413
Edgren Middle/High School	737, 739, 740, 741, 742, 746, 747	111,512
Mendel Elementary School	4306, 4307, 4315, 4319, 4320, 4360	115,257
Sollars Elementary School	80, 90, 92, 94, 98	151,612
Student Transportation Office Camp Zama	608	186
Student Transportation Office Misawa Air Base	1310	783
Student Transportation Office Yokota Air Base	4077, 4078	2,766
Yokota High School	4156, 4157, 4158, 4160, 4161, 4173, 4174	128,167
Yokota Middle School	4154, 4155	89,428
Yokota West Elementary School	1236, 1238, 1239	72,890
Zama Middle/High School	906, 910, 911, 912, 913, 914, 915, 917, 919, 919, 997, 998, 9131, 9132	168,348
Total		967,608

252.245-7004 DEV 2022-O0006

252.245-7004 Reporting, Reutilization, and Disposal.

As prescribed in 245.107(5), use the following clause:

REPORTING, REUTILIZATION, AND DISPOSAL (DEVIATION 2022-O0006)
(NOV 2021)

(a) *Definitions.* As used in this clause—